

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-019-19854-00-00

Spot: SESWNENW

Sec/Twnshp/Rge: 15-34S-12E

4094 feet from S Section Line, 3390 feet from E Section Line

Lease Name: WINDERS

Well #: 7

County: CHAUTAUQUA

Total Vertical Depth: 1060 feet

Operator License No.: 32619

Op Name: EXCEL OIL & GAS L.L.C.

Address: PO BOX 68
BUCYRUS, KS 66013

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10	20		
PROD	6	1060		

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 12/20/2011 12:00 AM

Plug Co. License No.: 32884

Plug Co. Name: ELMORE'S, INC.

Proposal Rcvd. from: MATT JONES

Company:

Phone: (620) 725-3636

Proposed Plugging Method: SURFACE CEMENT AND PRODUCTION CASING CEMENT UNKNOWN. RUN 1" TO TD. GEL HOLE. SPOT 20 SX OF CEMENT ON BOTTOM. PULL OUT AND PERFORATE @ 700' AND 350'. RUN 1" BACK IN AND PLUG W/ 20 SX @ 700'. PULL UP TO 350' AND CEMENT TO SURFACE.

Plugging Proposal Received By: DUANE SIMS

WitnessType: PARTIAL

Date/Time Plugging Completed 12/21/2011 12:00 PM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 950' gelled hole and spotted 20 sack plug. Pulled 1" and perforated casing at 700' and 350'. Ran 1" back into 700' and spotted 20 sack plug. Pulled up to 350' and circulated cement to surface inside and outside of casing. Pulled 1" and topped well off. A total of 150 sacks of cement were used to plug this well.

RECEIVED

MAR 29 2012 DAS


KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

RECEIVED Form CP-2/3

APR 30 2012

KCC WICHITA