

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-019-24268-00-00
Spot: SESWNWSE Sec/Twnshp/Rge: 15-35S-11E
1290 feet from S Section Line, 2261 feet from E Section Line
Lease Name: LEWIS Well #: 1
County: CHAUTAUQUA Total Vertical Depth: 2764 feet

Operator License No.: 34371
Op Name: DYNASTY DRILLING LLC
Address: PO BOX 4720
TULSA, OK 74159

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	40		30 SX
PROD	5.5	1890		295 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/01/2012 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: THOMAS H. OAST Company: _____ Phone: (620) 725-3200

Proposed Plugging Method: RUN 1" TUBING TO 1800'. GEL HOLE. SPOT 50' CEMENT AT 1800'. PULL TUBING TO 1370'. SPOT 50' CEMENT PLUG AT 1370'. PULL TUBING TO 350'. SPOT CEMENT FROM 350' TO SURFACE. CUT WELL CASING BELOW GROUND LEVEL. RESTORE LOCATION.

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE
Date/Time Plugging Completed 03/01/2012 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1780' gelled hole and spotted 12 sack plug. Pulled up to 1350' and spotted 7 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 54 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
1788	1794		
1350	1360		

RECEIVED

APR 20 2012

DAS

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed

Duane Sims 3/07/12

(TECHNICIAN)

RECEIVED Form CP-2/3

APR 30 2012

KCC WICHITA