

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-019-19868-00-00
Spot: SESENWNW Sec/Twnshp/Rge: 19-34S-12E
4196 feet from S Section Line, 4149 feet from E Section Line
Lease Name: BALES Well #: 3
County: CHAUTAUQUA Total Vertical Depth: 1166 feet

Operator License No.: 32255

Op Name: KANSAS ENERGY COMPANY, L.L.C.

Address: BOX 68
SEDAN, KS 67361

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|------|------------|-------------|---------|
| SURF | 10 | 20 | | 0 SX |
| PROD | 6 | 1166 | | 0 SX |

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 02/09/2012 12:00 AM

Plug Co. License No.: 32884

Plug Co. Name: ELMORE'S, INC.

Proposal Revd. from: MATT JONES

Company:

Phone: (620) 725-3636

Proposed Surface cement and production casing cement unknown. Run 1" to TD. Gel hole. Spot 20 sacks of cement on bottom. Pull out and perforate at 700' and 350'. Run 1" back in and plug with 20 sacks at 700'. Pull up to 350' and cement to surface.
Plugging
Method:

Plugging Proposal Received By: DUANE SIMS

WitnessType: PARTIAL

Date/Time Plugging Completed 02/10/2012 12:00 PM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1100' gelled hole and spotted 20 sack plug. Pulled 1" out of well. Perforated casing at 700' and 350'. Ran 1" to 700' and spotted 20 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 140 sacks of cement were used to plug this well.

Perfs:

RECEIVED

APR 18 2012 DAS


KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

RECEIVED

APR 30 2012

Form CP-2/3

KCC WICHITA