

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-125-02337-00-00

Spot: NWNWSESW

Sec/Twnshp/Rge: 28-33S-14E

1125 feet from S Section Line,

3755 feet from E Section Line

Lease Name: H D MARTIN

Well #: 37-28

County: MONTGOMERY

Total Vertical Depth: 700 feet

Operator License No.: 33991

Op Name: PITMAN, JOHN DOUGLAS REVOCABL

Address: 222 E. SHERIDAN #7

OKLAHOMA CITY, OK 73104

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6.25	700		

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/03/2011 12:00 AM

Plug Co. License No.: 32884

Plug Co. Name: ELMORE'S, INC.

Proposal Rcvd. from: GARY SHEARHART

Company:

Phone: (620) 330-1567

Proposed Plugging Method: RUN 1" TO BOTTOM, GEL HOLE, SPOT 20 SACKS OF CEMENT, PULL 1" OUT, PERFORATE CASING @ 250', RUN 1" BACK IN, CEMENT 250" TO SURFACE, INSIDE AND OUTSIDE OF CASING, PULL 1" OUT, TOP OFF WITH CEMENT.

Plugging Proposal Received By: DUANE SIMS

WitnessType: PARTIAL

Date/Time Plugging Completed 11/03/2011 2:00 PM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 700' gelled hole and spotted 20 sack plug. Pulled 1" and perforated casing at 250'. Ran 1" to 250' and circulated cement to surface inside and outside casing. Pulled 1" and topped well off. A total of 130 sacks of cement were used to plug this well.

RECEIVED

APR 19 2012 DAS

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed

Don a San 5/07/12

(TECHNICIAN)

RECEIVED CP-2/3

APR 30 2012

KCC WICHITA