

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-125-02335-00-00
Spot: SENESWSW Sec/Twnshp/Rge: 28-33S-14E
675 feet from S Section Line, 4201 feet from E Section Line
Lease Name: H D MARTIN Well #: 35-28
County: MONTGOMERY Total Vertical Depth: 735 feet

Operator License No.: 33991
Op Name: PITMAN, JOHN DOUGLAS REVOCABL
Address: 222 E. SHERIDAN #7
OKLAHOMA CITY, OK 73104

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6.25	735		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/01/2011 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: GARY SHEARHART Company: _____ Phone: (620) 330-1567

Proposed Plugging Method: RUN 1" TO BOTTOM, GELL HOLE, SPOT 20 SACKS OF CEMENT, PULL 1" OUT, PERFORATE CASINGT @ 250'.
RUN 1" BACK IN, CEMENT 250' TO SURFACE, INSIDE AND OUTSIDE OF CASING, PULL 1" OUT, TOP OFF
WITH CEMENT.

Plugging Proposal Received By: DUANE SIMS WitnessType: PARTIAL
Date/Time Plugging Completed 11/01/2011 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 735' gelled hole and spotted 20 sack plug. Pulled 1" and perforated casing at 250'.
Ran 1" to 250' and circulated cement to surface inside and outside of casing. Pulled 1" and
topped well off. A total of 130 sacks of cement were used to plug this well.

RECEIVED

APR 19 2012

DAS

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed

D G Sims 5/07/12

(TECHNICIAN)

RECEIVED

Form CP-2/3

APR 30 2012

KCC WICHITA