

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-125-01707-00-00

Spot: NENENWNE

Sec/Twnshp/Rge: 33-33S-14E

5094 feet from S Section Line, 1519 feet from E Section Line

Lease Name: BERRY A D

Well #: 5

County: MONTGOMERY

Total Vertical Depth: 775 feet

Operator License No.: 33991

String Size Depth (ft) Pulled (ft) Comment

Op Name: PITMAN, JOHN DOUGLAS REVOCABLE

PROD 6.25 775

Address: 222 E. SHERIDAN #7

OKLAHOMA CITY, OK 73104

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/09/2011 12:00 AM

Plug Co. License No.: 32884

Plug Co. Name: ELMORE'S, INC.

Proposal Rcvd. from: GARY SHEARHART

Company:

Phone: (620) 330-1567

Proposed
Plugging
Method:

RUN 1" TO BOTTOM, GELL HOLE, SPOT 20 SACKS OF CEMENT, PULL 1" OUT, PERFORATE CASING @ 250'
TO SURFACE, INSIDE AND OUTSIDE OF CASING, PULL 1" OUT, TOP OFF WITH CEMENT.

Plugging Proposal Received By: DUANE SIMS

WitnessType: NONE

Date/Time Plugging Completed 11/09/2011 12:00 PM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 775' gelled hole and spotted 20 sack plug. Pulled 1" and perforated casing at 250'.
Ran 1" to 250' and circulated cement to surface. Pulled 1" and topped well off. A total of 118
sacks of cement were used to plug this well.

RECEIVED

APR 19 2012

DAS

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed

Don G. Sim

(TECHNICIAN)

RECEIVED

APR 30 2012

Form CP-2/3

KCC WICHITA