

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-24018-00-00  
Spot: SENWNWSW Sec/Twnshp/Rge: 20-7S-18W  
2150 feet from S Section Line, 500 feet from W Section Line  
Lease Name: REED Well #: 1-20  
County: ROOKS Total Vertical Depth: 3500 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	267		185 SX
PROD	5.5	3500		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/20/2012 8:30 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix - 4% gel w/ 300 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: PARTIAL  
Date/Time Plugging Completed: 04/20/2012 5:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

CIBP @ 3070' - 5 sx cement  
Perforated. Shot 5 1/2" casing @ 1830', stuck gun equipment @ 1460' when coming out of hole.  
Pulled 1830' of 5 1/2" casing out of hole.  
Ran tubing in hole to 1813', pumped 185 sx cement w/100 # hulls.  
Pulled tubing to 1390', pumped 25 sx cement.  
Pulled tubing to 807', pumped 100 sx cement.  
Pulled tubing to 323', pumped 75 sx cement to circulate to surface.  
Pulled all tubing, topped off 8 5/8" surface pipe with 15 sx cement.

Perfs:

Top	Bot	Thru	Comments
3313	3319		
3198	3205		
3154	3159		
3122	3129		
3110	3118		

Remarks: SWIFT SERVICES TICKET # 21442

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

Pat Bedore  
(TECHNICIAN)

✓ 5/07/12

CM

RECEIVED

APR 30 2012

Form CP-2/3

KCC WICHITA

APR 25 2012