

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-097-20932-00-02  
Spot: NESWNWSE Sec/Twnshp/Rge: 26-30S-18W  
1975 feet from S Section Line, 2295 feet from E Section Line  
Lease Name: YOST Well #: 3  
County: KIOWA Total Vertical Depth: 5151 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4810		
CIBP		4950		
SURF	8.625	521		WITH 400 SX CMT
PROD	5.5	5149	1240	WITH 250 SX CMT

Well Type: EOR UIC Docket No: E24176.5 Date/Time to Plug: 04/19/2012 9:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2534

Proposed Plugging Method: SAND PERFS & 5 SX CMT. PLUG AT 1140' WITH 15 SX GEL & 50 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/19/2012 11:45 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SAND PERFS & 5 SX CMT AT 4810'. 1ST PLUG AT 1140' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 535' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 50 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5033	5042		
4881	4887		

Remarks: \*\*COMPLIANCE ISSUE: FAILED MIT\*\* USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

Signed

*[Signature]*  
(TECHNICIAN)  
*cc to WIC 4/23/12*

*3/14/12*

RECEIVED  
APR 25 2012  
KCC DODGE CITY

RECEIVED  
APR 30 2012  
KCC WICHITA