

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-21127-00-00  
Spot: NWSENEW Sec/Twnshp/Rge: 16-26S-8E  
4587 feet from S Section Line, 3028 feet from E Section Line  
Lease Name: LIGGETT Well #: 4  
County: BUTLER Total Vertical Depth: 2351 feet

Operator License No.: 30931  
Op Name: DAYSTAR PETROLEUM, INC.  
Address: 522 N. MAIN ST PO BOX 560  
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	130		57 SX
PROD	5.5	2565	800	100 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/01/2012 12:00 AM

Plug Co. License No.: 34685 Plug Co. Name: RCCA WELL SERVICE, LLC

Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: Per KCC District 2 requirements

Plugging Proposal Received By: DAN FOX

Witness Type: NONE

Date/Time Plugging Completed: 03/28/2012 2:30 PM

KCC Agent: PATRICK SHIELDS

Actual Plugging Report:

RAN 2" TUBING TO TD AND STACKED OUT. PULLED UP A JOINT AND SPOTTED A 25 SX PLUG OF 60 X 40 4% GEL @2350. TAGGED BOTTOM PLUG AT 2157'. SHOT CASING AND RECOVERED 800' OF 5.5 CASING. RAN TUBING BACK IN TO 250' AND CIRCULATED CEMENT TO SURFACE (98 SX). CONSOLIDATED TICKET #: 100055

Perfs:


Top	Bot	Thru	Comments
2452	2458	CSG	

Remarks: PLUGGING WAS UNWITNESSED DUE TO SCHEDULING CONFLICTS.

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

RECEIVED  
MAY 01 2012  
KCC-WICHITA

✓ 5/07/12

13