

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-20979-00-00
Spot: NWSENEW Sec/Twnshp/Rge: 16-26S-8E
683 feet from N Section Line, 2053 feet from W Section Line
Lease Name: LIGGETT Well #: 2
County: BUTLER Total Vertical Depth: 2565 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 522 N. MAIN ST PO BOX 560
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	125		100 SX
PROD	5.5	2564	800	100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/30/2012 12:00 AM

Plug Co. License No.: 34685 Plug Co. Name: RCCA WELL SERVICE, LLC

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: Per KCC District 2 requirements

Plugging Proposal Received By: DAN FOX

Witness Type: NONE

Date/Time Plugging Completed: 03/28/2012 2:30 PM

KCC Agent: PATRICK SHIELDS

Actual Plugging Report:

RAN 2" TUBING TO TD AND STACKED OUT. PULLED UP A JOINT AND SPOTTED A 25 SX PLUG OF 60X40 4% GEL @ 2400'. TAGGED BOTTOM PLUG AT 2345'. SHOT CASING AND RECOVERED 800' OF 5.5 CASING. RAN TUBING BACK IN TO 250' AND CIRCULATED CEMENT TO SURFACE (104 SX). CONSOLIDATED TICKET #: 100057

Perfs:

Top	Bot	Thru	Comments
2473	2477	CSG	
2453	2457	CSG	

RECEIVED

Remarks: PLUGGING WAS UNWITNESSED DUE TO SCHEDULING CONFLICTS.

MAY 01 2012

Plugged through: TBG

KCC WICHITA

District: 02

Signed

(TECHNICIAN)

5/07/12

JK