

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-21860-00-00
Spot: W2E2NWSE Sec/Twnshp/Rge: 13-28S-34W
2001 feet from S Section Line, 1696 feet from E Section Line
Lease Name: ROLLIE Well #: 13 #2
County: HASKELL Total Vertical Depth: 5700 feet

Operator License No.: 5278
Op Name: EOG RESOURCES, INC.
Address: 3817 NW EXPRESSWAY STE 500
OKLAHOMA CITY, OK 73112

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4061		WITH 10 SX CMT
CIBP		5355		
SURF	8.625	1615		WITH 480 SX CMT
PROD	5.5	5700	2040	WITH 285 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/24/2012 9:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Revd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 4122'. PLUG AT 1640' WITH 120 SX CMT. PLUG AT 850' WITH 60 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
Date/Time Plugging Completed: 04/24/2012 2:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4061' WITH 10 SX CMT. 1ST PLUG AT 1638' WITH 120 SX CMT. 2ND PLUG AT 850' WITH 60 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5386	5394		
4216	4244		

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

RECEIVED

MAY 01 2012

KCC WICHITA

District: 01

RECEIVED
APR 27 2012
KCC DODGE CITY

Signed Eric MacLaren
(TECHNICIAN)

Form CP-2/3

5/07/12