

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-22581-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 13-34S-38W
330 feet from N Section Line, 330 feet from W Section Line
Lease Name: RAYLEENE Well #: 13 #1
County: STEVENS Total Vertical Depth: 6800 feet

Operator License No.: 5278
Op Name: EOG RESOURCES, INC.
Address: 3817 NW EXPRESSWAY STE 500
OKLAHOMA CITY, OK 73112

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		6204		WITH 5 SX CMT
CIBP		6518		
SURF	8.625	1701		WITH 555 SX CMT
DVT		3228		
PROD	4.5	6794	1896	WITH 330 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/26/2012 9:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 6200' WITH 5 SX CMT. PLUG AT 1730' WITH 25 SX GEL & 120 SX CMT. PLUG AT 610' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/26/2012 2:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

SET CIBP @ 6204' WITH 5 SX CMT. 1ST PLUG AT 2390' WITH 60 SX CMT TO COVER DV TOOL SHOT 4 1/2" @ 1896' & POOH. 2ND PLUG RIH W/TBG TO 1738' & PUMPED 20 SX GEL & 120 SX CMT. 3RD PLUG AT 620' WITH 60 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6578	6594		
6268	6280		
6255	6263		
6254	6263		

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

RECEIVED
MAY 01 2012
KCC-WICHITA

District: 01

Signed

Jack MacLaskey
(TECHNICIAN)

RECEIVED

APR 27 2012

KCC DODGE CITY

Fom CP-2/3

5/07/12

ROR