

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-22806-00-00
Spot: E2SWNWSW Sec/Twnshp/Rge: 4-22S-14W
1650 feet from S Section Line, 4868 feet from E Section Line
Lease Name: UNRUH Well #: 3
County: STAFFORD Total Vertical Depth: 3900 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	251		WITH 180 SX CMT
PROD	5.5	3882	1852	WITH 100 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/25/2012 12:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2534

Proposed Plugging Method: SAND TO 3730' & 5 SX CMT. PLUG AT 870' WITH 13 SX GEL & 50 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/23/2012 2:30 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

Perfs:

SANDED BACK TO 3750' & 5 SX CMT WITH DUMP BAILER. 1ST PLUG AT 1780' WITH 20 SX GEL & 30 SX CMT DUE TO OIL FLOWING OUT OF CASING. 2ND PLUG AT 896' WITH 60 SX CMT. 3RD PLUG AT 289' WITH 60 SX CMT. 4TH PLUG AT 40' WITH 15 SX CMT.

Remarks: **COMPLIANCE ISSUE: NOV TA LTR** USED 60/40 POZMXI 4% GEL BY COPELAND ACID.

Plugged through: CSG

RECEIVED
MAY 01 2012
KCC WICHITA

District: 01

Signed

Richard M. Lacey

(TECHNICIAN)

RECEIVED

APR 27 2012

KCC DODGE CITY

Form CP-2/3

5/07/12

AMUP