

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-25380-00-00  
Spot: SWNWSENE Sec/Twnshp/Rge: 20-18S-21W  
1658 feet from N Section Line, 1213 feet from E Section Line  
Lease Name: SLOVER "S" Well #: 1  
County: NESS Total Vertical Depth: 4340 feet

Operator License No.: 30742  
Op Name: PALOMINO PETROLEUM, INC.  
Address: 4924 SE 84TH ST  
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1422		WITH 650 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/27/2012 4:00 AM  
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC  
Proposal Rcvd. from: MARK BIGGIE Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: 1ST PLUG AT 1470' WITH 50 SX CMT. 2ND PLUG AT 720' WITH 40 SX CMT. 3RD PLUG AT 270' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: NONE  
Date/Time Plugging Completed: 04/27/2012 6:00 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

Perfs:

1ST PLUG AT 1470' WITH 50 SX CMT. 2ND PLUG AT 720' WITH 40 SX CMT. 3RD PLUG AT 270' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: DP

District: 01

RECEIVED

APR 27 2012

KCC DODGE CITY

Signed

*Kenny Sullivan*  
(TECHNICIAN) *5/07/12*

RECEIVED

MAY 01 2012

KCC WICHITA

Form CP-2/3

*13912*