

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-21144-00-00  
Spot: E2SWNE Sec/Twnshp/Rge: 14-34S-34W  
3306 feet from S Section Line, 1665 feet from E Section Line  
Lease Name: STEPHENS Well #: 1-14  
County: SEWARD Total Vertical Depth: 6600 feet

Operator License No.: 3988  
Op Name: SLAWSON EXPLORATION COMPANY.  
Address: 204 N ROBINSON AVE STE 2300  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		6300		
SURF	8.625	1658		WITH 715 SX CMT
COND	20	54		SX
PROD	4.5	6595	2500	WITH 250 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/23/2012 8:30 AM  
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.  
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PUMP 100 SX HULLS @ 20 SX CMT AT 6135'. PLUG AT 1690' WITH 50 SX CMT. PLUG AT 550' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/23/2012 3:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

PUMP 200 SX HULL & 20 SX CMT AT 6135'. 1ST PLUG AT 1690' WITH 50 SX CMT.  
2ND PLUG AT 550' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6493	6500		
6135	6148		

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

Signed

Jack MacLaskey  
(TECHNICIAN)

RECEIVED

APR 27 2012

KCC DODGE CITY

RECEIVED  
MAY 01 2012  
KCC WICHITA

5/14/12  
Form CP-2/3