

KANSAS CORPORATION COMMISSION ONE POINT STABILIZED OPEN FLOW OR DELIVERABILITY TEST

Type Test:

- Open Flow
 Deliverability

(See Instructions on Reverse Side)

Test Date:
7-12-11

API No. 15

15-119-21247 - 0000

Company OOLITE ENERGY, LLC		Lease BURMEISTER			Well Number 1-24
County MEAD	Location 1650 FNL & 2299 FEL	Section 24	TWP 33S	RNG (E/W) 30W	Acres Attributed
Field		Reservoir MORROW/CHESTER	Gas Gathering Connection DCP		
Completion Date 2-2-10		Plug Back Total Depth 6068		Packer Set at NONE	
Casing Size 5.5	Weight 15.5	Internal Diameter 4.950	Set at 6124	Perforations 5833	To 5918
Tubing Size 2.875	Weight 6.5	Internal Diameter 2.441	Set at 5858	Perforations	To
Type Completion (Describe) COMINGELD GAS		Type Fluid Production WATER/OIL		Pump Unit or Traveling Plunger? Yes / No NO	
Producing Thru (Annulus / Tubing) TUBING		% Carbon Dioxide	% Nitrogen	Gas Gravity - G _g 0.693	
Vertical Depth(H) 5876		Pressure Taps FLANGE		(Meter Run) (Prover) Size 3.068"	
Pressure Buildup: Shut In 7-8-11 20 at 0815 (AM) (PM) Taken 7-11-11 20 at 0815 (AM) (PM)					
Well on Line: Started 7-11-11 20 at 0815 (AM) (PM) Taken 7-12-11 20 at 0815 (AM) (PM)					

OBSERVED SURFACE DATA

Duration of Shut-in **72.0** Hours

Static / Dynamic Property	Orifice Size (Inches)	Circle one: Meter or Prover Pressure psig (P _m)	Pressure Differential in Inches H ₂ O	Flowing Temperature t	Well Head Temperature t	Casing Wellhead Pressure (P _w) or (P _c) or (P _e)		Tubing Wellhead Pressure (P _w) or (P _t) or (P _e)		Duration (Hours)	Liquid Produced (Barrels)
						psig	psia	psig	psia		
Shut-in						580.0	594.4	578.2	592.6	72.0	
Flow	1.500	86.9	15.3	76	75	298.4	312.8	199.3	213.7	24.0	10.0

FLOW STREAM ATTRIBUTES

Plate Coefficient (F _o) (F _a) Mcfd	Circle one: Meter or Prover Pressure psia	Press Extension $\sqrt{P_m \times h}$	Gravity Factor F _g	Flowing Temperature Factor F _t	Deviation Factor F _{ov}	Metered Flow R (Mcfd)	GOR (Cubic Feet/ Barrel)	Flowing Fluid Gravity G _m
11.4128	101.30	39.37	1.2012	0.9850	1.0102	537.0	NONE	0.693

(OPEN FLOW) (DELIVERABILITY) CALCULATIONS

(P_e)² = **353.3** ; (P_w)² = **97.8** ; P_o = **52.6** % (P_c - 14.4) + 14.4 = **594.4** ; (P_e)² = 0.207 ; (P_o)² = _____

(P _e) ² - (P _w) ² or (P _e) ² - (P _o) ²	(P _e) ² - (P _w) ²	Choose formula 1 or 2: 1. P _e ² - P _w ² 2. P _e ² - P _o ² divided by: P _e ² - P _w ²	LOG of formula 1. or 2. and divide by: $\frac{P_e^2 - P_w^2}{P_e^2 - P_o^2}$	Backpressure Curve Slope = "n" or Assigned Standard Slope	n x LOG []	Antilog	Open Flow Deliverability Equals R x Antilog (Mcfd)
353.10	255.47	1.382	0.1406	0.625	0.0879	1.2242	657.44

Open Flow **657** Mcfd @ 14.65 psia Deliverability Mcfd @ 14.65 psia

The undersigned authority, on behalf of the Company, states that he is duly authorized to make the above report and that he has knowledge of the facts stated therein, and that said report is true and correct. Executed this the 12 day of JULY, 20 11.

Copy to KCC Wichita
Witness (if any)

Copy to KCC Dodge City
For Commission

Precision Wire Line & Testers
For Company

Markus Kouch
Checked by

RECEIVED

JUL 21 2011

KCC WICHITA

I declare under penalty of perjury under the laws of the state of Kansas that I am authorized to request exempt status under Rule K.A.R. 82-3-304 on behalf of the operator _____ and that the foregoing pressure information and statements contained on this application form are true and correct to the best of my knowledge and belief based upon available production summaries and lease records of equipment installation and/or upon type of completion or upon use being made of the gas well herein named.

I hereby request a one-year exemption from open flow testing for the _____ gas well on the grounds that said well:

(Check one)

- is a coalbed methane producer
- is cycled on plunger lift due to water
- is a source of natural gas for injection into an oil reservoir undergoing ER
- is on vacuum at the present time; KCC approval Docket No. _____
- is not capable of producing at a daily rate in excess of 250 mcf/D

I further agree to supply to the best of my ability any and all supporting documents deemed by Commission staff as necessary to corroborate this claim for exemption from testing.

Date: _____

Signature: _____

Title: _____

Instructions: If a gas well meets one of the eligibility criteria set out in KCC regulation K.A.R. 82-3-304, the operator may complete the statement provided above in order to claim exempt status for the gas well.

At some point during the current calendar year, wellhead shut-in pressure shall have been measured after a minimum of 24 hours shut-in/buildup time and shall be reported on the front side of this form under **OBSERVED SURFACE DATA**. Shut-in pressure shall thereafter be reported yearly in the same manner for so long as the gas well continues to meet the eligibility criterion or until the claim of eligibility for exemption **IS** denied.

The G-2 form conveying the newest shut-in pressure reading shall be filed with the Wichita office no later than December 31 of the year for which it's intended to acquire exempt status for the subject well. The form must be signed and dated on the front side as though it was a verified report of annual test results.