

KCC OIL/GAS REGULATORY OFFICES

Date: 04/17/12

District: 1

Case #: \_\_\_\_\_

- New Situation
- Response to Request
- Follow-Up

- Lease Inspection
- Complaint
- Field Report

Operator License No: 4767  
 Op Name: Ritchie Exploration, Inc.  
 Address 1: 8100 E. 22nd St. N., #700  
 Address 2: Box 783188  
 City: Wichita  
 State: KS Zip Code: 67278 -3188  
 Operator Phone #: (316) 691-9500

API Well Number: 15-057-20792-00-00  
 Spot: NE-SW Sec 2 Twp 26 S Rng 22  E /  W  
1990 Feet from  N /  S Line of Section  
2290 Feet from  E /  W Line of Section  
 GPS: Lat: 37.81251 Long: 99.69741 Date: 4/17/12  
 Lease Name: Peintner 2C Well #: 1  
 County: Ford

Reason for Investigation:

Company requested a state witness to the alternate II cementing job.

Problem:

Alternate II cementing requirements have not been met.

Persons Contacted:

Gary Rowe.

Findings:

8 5/8" was set @ 337' with 230 sx cement. 4 1/2" was set @ 4957' with 200 sx cement on the primary cementing job. Company opened port collar @ 1434'. Basic Energy Services, L.L.C. pumped 195 sx cement, circulating 15 sx to the pit. Closed port collar.

Action/Recommendations:

Follow Up Required  Yes  No

Date: \_\_\_\_\_

None. Alternate II cementing requirements have been met.

60/40 poz, 6% gel, 175# hulls by Basic Energy Services, L.L.C.

GPS converted footages are 1989' FSL & 2281' FWL.

RECEIVED  
APR 30 2012  
KCC WICHITA

Verification Sources:

Photos Taken: 0

- RBDMS
- T-I Database
- Other: On-site witness
- KGS
- District Files
- TA Program
- Courthouse

By: Eric Maclaren  
Eric Maclaren

Retain 1 Copy District Office  
Send 1 Copy to Conservation Division

RECEIVED  
APR 24 2012

Form: \_\_\_\_\_

KCC DODGE CITY

Ray