

KCC OIL/GAS REGULATORY OFFICES

Date: 03/26/12

District: 1

Case #: _____

- New Situation
- Response to Request
- Follow-Up

- Lease Inspection
- Complaint
- Field Report

Operator License No: 4058

API Well Number: 15-083-21759-00-00

Op Name: American Warrior, Inc.

Spot: NW-NW-SE-SW Sec 4 Twp 24 S Rng 21 E / W

Address 1: 3118 Cummings Rd.

1000 Feet from N / S Line of Section

Address 2: P.O. Box 399

1625 Feet from E / W Line of Section

City: Garden City

GPS: Lat: 37.98843 Long: 99.63721 Date: 3/21/12

State: KS Zip Code: 67846 -0399

Lease Name: Burke-Jacobs Well #: 1-4

Operator Phone #: (620) 275-2963

County: Hodgeman

Reason for Investigation:

Company requested a state witness to the alternate II cementing job.

Problem:

Alternate II cementing requirements have not been met.

Persons Contacted:

Joe Smith.

Findings:

Originally, this was scheduled 3/21/12, but was postponed due to rain. American Warrior never called the district office to reschedule this job. 8 5/8" was set @ 214' with 150 sx cement. 5 1/2" was set @ 4654' with 125 sx cement on the primary cementing job. 3/26/12 Company opened port collar @ 1435'. Swift Services, Inc. pumped 175 sx SMD cement, but had no circulation. Closed port collar. CBL showed TOC @ 908'. 3/30/12 Perforated @ 600' & pumped 150 sx cement with no circulation. CBL showed TOC @ 500'. 4/2/12 Perforated @ 495' & pumped 140 sx cement with no circulation. Pumped 10 sx cement down the backside and it pressured to 500# and held.

Action/Recommendations:

Follow Up Required Yes No

Date: _____

None. Alternate II cementing requirements have been met.
GPS converted footages are 1009' FSL & 1606' FWL.

Verification Sources:

Photos Taken: 0

- RBDMS
- T-I Database
- Other: Partial on-site witness.
- KGS
- District Files
- TA Program
- Courthouse

By: Eric MacLaren
Eric MacLaren

Retain 1 Copy District Office
Send 1 Copy to Conservation Division

RECEIVED

APR 16 2012

KCC WICHITA

Form: _____

WOW