

KCC OIL/GAS REGULATORY OFFICE

ALT 2

DATE: 11/9/93

[X] New Situation
[] Response to Request
[] Follow-Up

LOCATION W/2 NE NE, SEC 23, T 17 S, R 26W

OPERATOR: Pickrell Drilling Company, Inc.

LICENSE #: 5123

ADDRESS: 110 N. Market, Ste. 205

LEASE/WELL NUMBER: Bauer Tr. J #1

ADDRESS: Wichita, KS 67202

COUNTY: Ness

PHONE #: 316-262-8427

API#15-135-23,788-~~0000~~

LEASE INSPECTION: COMPLAINT: FIELD REPORT: X

REASON FOR INVESTIGATION: Pickrell called the district office to report the completion of this well.

PROBLEM: The Alternate II cementing had not been done.

PERSONS CONTACTED: Ed Mondero & Doyle Folkert with Pickrell

FINDINGS: The port collar on the 4 1/2" casing was set at 1805' with a cement basket set at 1805'. The collar was opened and 400 sx of 60/40 Pozmix 8% gel 1/4# floseal were pumped. The job circulated 14 bbl. of cement to the pit.

PHOTOS TAKEN:

ACTION/RECOMMENDATIONS: The Alternate II cementing requirements were met. Case closed.

RECEIVED
STATE CORPORATION COMMISSION

NOV 16 1993

CONSERVATION DIVISION
Wichita, Kansas

Richard Lacey

11/9/93