

TYPE

AFFIDAVIT OF COMPLETION FORM

ACO-1 WELL HISTORY

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed. Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 5073 EXPIRATION DATE 6-30-83

OPERATOR Eagle Explorations, Inc. API NO. 15-135-22,360-0000

ADDRESS Suite 300, 107 N. Market COUNTY Ness

Wichita, Kansas 67202 FIELD Dumler

** CONTACT PERSON Carl Durr PROD. FORMATION None

PHONE 316-265-2897

PURCHASER None LEASE Stutz

ADDRESS WELL NO. 1

DRILLING CONTRACTOR Carlyle Drilling, Inc. 825 Ft. from North Line and

ADDRESS Suite 300 107 N. Market 1320 Ft. from East Line of

Wichita, Kansas 67202 the N/W (Qtr.) SEC 12 TWP 17S RGE 26W.

PLUGGING CONTRACTOR Same As Above WELL PLAT

ADDRESS

(Office Use Only)

KCC

KGS

SWD/REP

PLG.

TOTAL DEPTH 4525 PBTD

SPUD DATE 2-10-83 DATE COMPLETED

ELEV: GR 2509 DF 2521 KB 2523

DRILLED WITH (CABLE) ROTARY (AIR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE

Amount of surface pipe set and cemented 290 DV Tool Used? No

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, Dry Disposal, Injection, Temporarily Abandoned, OWWO. Other

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

RECEIVED STATE CORPORATION COMMISSION

FEB 28 1983

CONSERVATION DIVISION Wichita, Kansas certifies

A F F I D A V I T

Carl Durr, being of lawful age, certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.


Carl Durr Carl Durr (Name)

SUBSCRIBED AND SWORN TO BEFORE ME this 24th day of February, 1983.

Sharon J. Clark (NOTARY PUBLIC)

MY COMMISSION EXPIRES: March 16, 1983

** The person who can be reached by phone regarding any questions concerning this information.



FILL IN WELL LOG AS REQUIRED:

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
D.S.T. #1 4439'-4460' 30-60-60-90 IFP: 20-20 FFP: 20-20 ISIP: 39 FSIP: 29 Recovered: 1' Drilling Mud			Topeka Heebner Toronto L.K.C. B.K.C. Marmaton Ft. Scott Cherokee Sh. Miss.	3546' 3817' 3836' 3857' 4164' 4208' 4360' 4384' 4452'
D.S.T. #2 4460'-4480' 30-60-60-90 IFP: 20-59 FFP: 39-78 ISIP: 703 FSIP: 645 Recovered: 20' clean oil, 70' muddy water with oil specks				
MISSISSIPPIAN: Dolo wh-lt tan Med. xln. w/vug Ø, Blk sat. stn. Dark free oil				

Report of all strings set— surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Socks	Type and percent additives
Surface	12 1/4"	8 5/8"	24	290	Common	200	2% Gel. 3% CaCl ₂

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Socks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

Date of first production

Producing method (flowing, pumping, gas lift, etc.)

Gravity

RATE OF PRODUCTION PER 24 HOURS

Oil

Gas

Water

%

Gas-oil ratio

Disposition of gas (vented, used on lease or sold)

MCY

bbbl

bbbl

CFPB

Perforations

None