

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-051-249800000

LEASE NAME Victoria North
Ext. "C"

WELL NUMBER 1
3,250 Ft. from S Section Line
330 Ft. from E Section Line

SEC. 3 TWP. 13 RGE. 16 (E) or (W)

COUNTY Ellis

Date Well Completed 9-3-97

Plugging Commenced 9-3-97

Plugging Completed 9-4-97

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR ESP DEVELOPMENT, INC.

ADDRESS 17746 177th Blvd., Paradise, KS. 67658

PHONE#(913) 998-4413 OPERATORS LICENSE NO. 6194

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-3-97 (date)

by Ed Schumacher (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 3,490'

Show depth and thickness of all water, oil and gas formations.

9-12-97

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	211'	Cmtd. w/140 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each section. Spot 20 sax cement @3,483'. Push bridge plug to 1,140', spot 20 sax cement on plug thru drill pipe. Push plug to 600', pump 100 sax cement on plug thru drill pipe. Push bridge plug to 260', pump 40 sax cement on plug thru drill pipe. Push wiper plug to 40', dump 10 sax cement on plug to cellar. Dump 10 sax cement down mouse hole and 15 sax cement down rat hole

Name of Plugging Contractor Shields Drilling Co. License No. 5184

Address PO Box 709, Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ESP DEVELOPMENT, INC.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas Contractor

(Employee of ~~Operator~~) or ~~Operator~~) c above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman
Shields Bldg.
(Address) PO Box 709, Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 8th day of September, 19 97

Ruth Phillips
Notary Public

My Commission Expires: _____





Shields

WELL LOG


15-051-24980-00-00

ORIGINAL

Russell, Kansas

Operator: ESP Development, Inc.
 Well: Victoria North Ext. "C" #1
 Commenced: August 28, 1997
 Completed: September 4, 1997
 Contractor: Shields Drilling Co.

Well Description: 50' South of
 C E/2 SE NE
 Sec. 3-13S-16W
 Ellis County, KS.



CASING RECORD

Size	Run	Pulled
8 5/8"	211'	Cmtd. w/140 sax

Elevation: 1,999' KB

Treatment:

Production:

Tops:

..... Figures Indicate Bottom of Formations

Shale	214'	
Sand and shale	1,126'	
Anhydrite	1,165'	
Shale	2,600'	
Shale & lime	3,105'	
Lime	3,490'	RTD

Notes