

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

15-051-06004-0000
WELL PLUGGING RECORD

Ellis County, Sec. 32 Twp. 11 Rge. (E) 17 (W)

Location as "NE/CNW/SW" or footage from lines City NW NE
Lease Owner Barnett Oil Company, et al
Lease Name Shutts Well No. 1
Office Address 417 First Nat'l Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed March 29 1940
Application for plugging filed April 3, 1952
Application for plugging approved April 3, 1952
Plugging commenced April 3, 1952
Plugging completed April 3, 1952
Reason for abandonment of well or producing formation excessive salt water in Arbuckle Lime formation, well being operated at a loss.
If a producing well is abandoned, date of last production December 11, 1951
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Arbuckle Depth to top 3597 Bottom 3628 Total Depth of Well 3628 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Casing			1208	10 3/4"	1208	None
Oil String			3598	5 1/2"	3598	3000

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set Lane Wells Plug at 3436 feet and tested K.C. Lime formation. Set second Lane Wells Plug at 3388 and tested K.C. Lime formation, well making water, to be abandoned. Filled casing with mud to 3300 feet. Dumped 4 sacks of cement at 3300 feet. Shot oil string off at 3000 feet and pulled 5 1/2" casing. Filled hole and surface pipe with mud to 300 feet. Set rock bridge at 300 feet and filled surface casing with 20 sacks of cement to 258 feet. Filled surface pipe with mud from 258 feet to 30 feet. Set plug and filled surface casing with 10 sacks of cement to bottom of cellar.

RECEIVED
CORPORATION COMMISSION

MAY 26 1952

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bert Self
Address Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
W. R. Hunter (employee of owner) or owner or operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) W. R. Hunter
417 First Nat'l Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of May, 19 52

My commission expires February 27, 1956.

Mildred F. Willis Notary Public.

24-2675-B 2-52-20M



15-051-06004-0000

BARNETT OIL COMPANY, ET AL
LOG OF SHUTTS WELL NO. 1
CENTER NORTH LINE NW 1/4 NE 1/4
SECTION 32-118-17W, ELLIS COUNTY, KANSAS

DATE COMMENCED: February 23, 1940

DATE COMPLETED: March 29, 1940

Formation	From	To	Remarks
Sand, Rock and Clay	0	110	
Shale and Lime Shells	110	610	
Shale and Shells	610	635	
Sand and Shale	635	700	
Shale and Shells	700	880	
Sand	880	975	
Lime	975	1050	
Shale and Red Bed	1050	1100	
Red Bed	1100	1210	
Red Bed and Shale	1210	1275	
Shale	1275	1285	
Red Bed	1285	1320	
Anhydrite	1320	1405	Set 10 3/4" Surface Pipe at 1208 feet; cemented with 450 sacks of cement.
Red Bed and Shells	1405	1445	
Shale and Shells	1445	1530	
Red Bed and Shale	1530	1575	
Shale and Shells	1575	1735	
Shale and Salt	1735	1890	
Shale	1890	1945	
Lime	1945	2030	
Lime and Shale	2030	2105	
Shale and Shells	2105	2160	
Lime	2160	2240	
Lime and Shale	2240	2305	
Lime	2305	2410	
Broken Lime	2410	2425	
Lime and Shale	2425	2470	
Lime	2470	2490	
Shale	2490	2510	
Lime	2510	2525	
Lime and Shale	2525	2690	
Shale	2690	2865	
Lime	2865	2882	
Shale and Lime	2882	3000	
Shale	3000	3060	
Lime	3060	3247	
Shale - soft	3247	3251	
Lime	3251	3628	
Total Depth		3628	Set 5 1/2" Casing at 3598 feet; cemented with 100 sacks of cement.

Plugged Back (to test K.C. Lime) -

Set Lane Wells Plug 3436
 Set Second Lane Wells Plug 3388
 Dry and abandoned in K.C. Lime 3388
 5" Casing Shot off and Pulled 3000
 Plugged and abandoned - April 3, 1952.

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 26 1952
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC-17-11-17W
 BOOK PAGE 8 LINE 10