

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

15-051-03415-0000
WELL PLUGGING RECORD

Ellis County, Sec. 32 Twp. 11 Rge. (E) 17 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE $\frac{1}{4}$ NW $\frac{1}{4}$ NE $\frac{1}{4}$

Lease Owner Mallard Drilling Company

Lease Name Shutts Well No. 1

Office Address 1016 Union National Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 6-30 19 53

Application for plugging filed 6-30 19 53

Application for plugging approved 6-30 19 53

Plugging commenced 6-30 19 53

Plugging completed 6-30 19 53

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3656 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				10-3/4"	238'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 225'
Bottom plug @ 225' with 20 Sx Cement.
Top plug @ 35' with 10 Sx Cement

07-06-53

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lewis Drilling Co.

Address 607 Union National Bank Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

L. L. Bailey (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. L. Bailey

607 Union National Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of July 19 53

Arthur P. Derrington
Notary Public.

My commission expires August 20, 1956

23-8390-s 6-51-20M

PLUGGING
FILE SEC 32 T 11 R 17W
BOOK PAGE 112 LINE 3

WELL LOG 15-051-03615-0000

COMPANY Mallard Drilling Company

SEC. 32 T. 11 R. 17W

FARM Shutts NO. 1

LOC. SE 1/4 NW 1/4 NE 1/4

TOTAL DEPTH 3656'


COMM. 6-18-53

COMP. 6-30-53

COUNTY Ellis KANSAS

SHOT OR TREATED CONTRACTOR Lewis Drilling Co.

ISSUED



CASING

20 XX 10-3/4" 238'
15 B
12 6
13 5

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

0 - 238 Sand & Shale
238 - 1360 Shale & Shells
1360 - 1375 Anhydrite
1375 - 1400 Shale & Shells
1400 - 2305 Lime & Shale
2305 - 2410 Lime
2410 - 2650 Lime & Shale
2650 - 2760 Broken Lime
2760 - 3150 Shale & Lime
3150 - 3295 Lime
3295 - 3355 Shale & Lime
3355 - 3602 Lime
3602 - 3635 Conglomerate
3635 - 3656 Lime
3656 TD

State of KANSAS
County of SEDGWICK } ss:

I, L. L. Bailey of the Lewis Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Shutts #1 well.

PLUGGING
FILE SEC 32 T 11 R 17W
BOOK PAGE 112 LINE 3

Subscribed and sworn to before me this 2nd day of July 1953

My Commission Expires: August 20, 1956

Arthur P. Harrington
NOTARY PUBLIC