


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

15051055740000
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines Ellis County. Sec. 32 Twp. 11S Rge. 17E (W)
SE/4
Lease Owner Phillips Petroleum Company
Lease Name Kessler Well No. 3
Office Address Box 779, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed April 22, 19 48
Application for plugging filed October 22, 19 51
Application for plugging approved October 24, 19 51
Plugging commenced November 5, 19 51
Plugging completed November 8, 19 51
Reason for abandonment of well or producing formation Uneconomical to operate.

If a producing well is abandoned, date of last production May 12, 19 51
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation Arbuckle Depth to top 3589' Bottom 3670' Total Depth of Well 3670' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Anhydrite	Dry	1315'	- -	8-5/8"	1362.94'	None
Lansing-Kansas City	Dry	3328	- -	5-1/2"	3616.32'	2594.00'
Arbuckle	Oil	3589'	3670'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped 20 sx. cement 3670' - 3520'. Mudded hole to 250' - dumped rock from 250' to 235'. Dumped 15 sx. cement in filling to 160'. Mudded hole to 35' and dumped 10 sx. cement in filling to base of cellar. Well plugged & abandoned 2:00 P.M. 11-8-51.

11-13-51

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
A. J. Willis (employee of owner) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. J. Willis

Box 779, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 9th day of November, 19 51

My commission expires November 18, 1953 Notary Public.

NOV 18 1953
COOK

Formation Record

Lease Kessler

Well No. 3

15:051-05574-0000

FROM	TO	Formation	REMARKS
0	55	Surface Soil	ELEVATION: 2059.8' R.T.B.
55	198	Sand and Shells	
198	1010	Shale and Shells	
1010	1315	Shale and Red Bed	
1315	1360	Anhydrite	Top Anhydrite 1315'
1360	1371	Shale	
1371	1598	Shale and Shells	
1598	1988	Shale and Sand	
1988	2135	Shale	
2135	2268	Lime and Shale	
2268	2352	Lime	
2352	2612	Lime and Shale	
2612	2667	Shale	
2667	3108	Lime and Shale	
3108	3130	Lime	
3130	3493	Lime and Shale	Top Lansing-Kansas City 3328'
3493	3503	Lime	
3503	3589	Lime and Shale	Top Arbuckle 3589'
3589	3670	Lime	
	3670	T.D.	

PLUGGING

FILE SEC 32, 11 ROW

BOOK PAGE 19 LINE 1