

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-051-25168-0000

LEASE NAME Kessler

WELL NUMBER 5

330 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 32 TWP. 11S RGE. 17W (E) or (W)

COUNTY Ellis

Date Well Completed 11/8/02

Plugging Commenced 6:15am 11/8/02

Plugging Completed 9:00am 11/8/02

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.
JAN 08 2003
KCC WICHITA
LEASE OPERATOR Elysium Energy, L.L.C.

ADDRESS 1625 Broadway, Suite 2000, Denver, CO 80202

PHONE# (303) 389-3610 OPERATORS LICENSE NO. 32754

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11/7/02 (date)
by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? Yes if not, is well log attached? _____

Producing Formation None Depth to Top _____ Bottom _____ T.O. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From Surf.	To 225	Size 8-5/8"	Put in 225.12	Pulled out None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.

- 1st Plug @ 1350' w/50 sx 10 sx in mouse hole Circulated 1st plug 15 minutes with 48 viscosity mud
- 2nd Plug @ 800' w/100 sx 15 sx in rat hole Plugs displaced with mud
- 3rd Plug @ 275' w/40 sx Total of 225 sx 60/40 Poz 6% gel w/1/4# per sx EC by Allied Cementing
- 4th Plug @ 40' w/10 sx Completed @ 9:00 am on 11/8/02

Name of Plugging Contractor Discovery Drilling Co., Inc. License No. 31548

Address P.O. Box 763 Hayes, KS 67601


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Elysium Energy, L.L.C.

STATE OF Colorado COUNTY OF Denver, ss.

James Annable (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 1625 Broadway, Suite 2000, Denver, CO 80202



WITNESSED AND SWORN TO before me this 6th day of January, 2003

My Commission Expires 10/29/2005 [Signature] Notary Public

My Commission Expires: 10/29/05

OR