


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Ellis County, Sec. 36 Twp. 11 Rge. 17 (NW 1/4)(W)
Location as "NE/CNW 1/4 SW 1/4" or footage from lines 50' E. of C. of SE SE 1/4
Lease Owner Anderson-Prichard Oil Corp.
Lease Name Samuelson Well No. 5
Office Address Box 142 - Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 14, 1950
Application for plugging filed January 14, (Verbal) 1950
Application for plugging approved January 14, (Verbal) 1950
Plugging commenced January 14, 1950
Plugging completed January 14, 1950
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19...
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3646' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	12 1/4'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from...feet to...feet for each plug set.

Filled with Heavy Mud to 250'
Halliburton Plug at 250'
15 Sx Cement on top of plug
Filled with Heavy mud to 40'
Halliburton plug at 40'
10 sax cement on top of plug to surface
Tied top plug with wire

1-26-50

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Anderson-Prichard Oil Corporation
Address Box 142 - Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Gerald L. Dougherty (employee of owner)

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gerald M. Dougherty
Box 142 - Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 25th day of January, 1950

My commission expires April 26 1952
Gerald M. Landick Notary Public.

PLUGGING
PER SEC 36 T 11 R 17 W
BOOK PAGE 134 LINE 11

SAMUELSON NO. 5 WELL

LOCATION: SE $\frac{1}{4}$ SE $\frac{1}{4}$ NW $\frac{1}{4}$ Sec. 36-11S-17W
Ellis County, Kansas. DATE SPUDDED: 12-29-49

OPERATOR: Anderson-Prichard Oil Corporation COMPLETED: 1-14-50

CONTRACTOR: Birmingham-Bartlett Drilling Co.

SURFACE CASING: Ran 56' jts., 1218' 8-5/8", 28.55#
casing cemented @ 1218' with 600
sacks bulk cement.

OIL STRING: None. D & A.

L O G

(Figures indicate bottom of formation)

0	to	570	Shale and shells
		650	Sand
		995	Shale and shells
		1208	Red Rock
		1245	Anhydrite
		1880	Shale and shells
		1955	Lime and shale
		2165	Broken lime
		2260	Lime
		2315	Broken lime
		2615	Lime and shale
		2885	Shale and shells
		2980	Shale and lime
		3470	Lime
		3508	Conglomerate and lime
		3548	Conglomerate
		3565	Conglomerate and Arbuckle
		3580	Arbuckle
		3646	Lime
		3646	Total Depth

The undersigned Richard Hindery of the Birmingham-Bartlett Drilling Co. hereby certifies that the above is a true and correct log of the formations encountered in drilling the Samuelson No. 5 as shown on the daily drilling reports.

BIRMINGHAM-BARTLETT DRILLING CO.

BY Richard Hindery

Subscribed and sworn before me
this 16th day of January, 1950.

Virgil Z. Ginger
Notary Public

My commission expires November 29, 1950.

