


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Ellis County, Sec. 36 Twp. 11S Rge. (E) 17 (W)
Location as "NE/CNW/SW" or footage from lines SE NW SW
Lease Owner Rocket-Schusterman Oil Account
Lease Name Hall Well No. 3
Office Address 1209 Mid Continent Bldg., Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 2/7/ 1970
Application for plugging filed (letter 2/10/70) 2/7/ 1970
Application for plugging approved 2/7/ 1970
Plugging commenced 2/7/ 1970
Plugging completed 2/7/ 1970
Reason for abandonment of well or producing formation



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 3717 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	252'	8-5/8"	252'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 720 feet. Set first plug at 720 feet with 70 sacks cement.
Filled hole with heavy mud to 240 feet. Set second plug at 240 feet with 20 sacks cement.
Filled hole with heavy mud to 40 feet. Set third plug at 40 feet with 10 sacks cement.
Job complete at 8:45 AM, February 7, 1970.


RECEIVED
STATE CORPORATION COMMISSION
FEB 11 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.
Address 830 Sutton Place - Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick ss.
Emmet E. Hall (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Emmet E. Hall
830 Sutton Place - Wichita, Kansas 67202
(Address)



SUBSCRIBED AND SWORN to before me this 10 day of February, 1970
Barbara J. Layton
Notary Public.

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

HALL #3
 SE NW SW Section 36-11S-17W
 Ellis County, Kansas

Commenced: January 30, 1970
 Completed: February 7, 1970

OPERATOR - Rocket-Schusterman Oil Account

DEPTH		FORMATION	REMARKS
From	To		
0	255	Surface soil, sand and shale	Ran 12 joints 8-5/8" casing, set @ 252' w/175 sacks cement.
255	651	Shale and shells	
651	791	Sand	
791	1315	Shale and red bed	
1315	1356	Anhydrite	
1356	1920	Shale and shells	
1920	3265	Shale and lime	
3265	3650	Lime	
3650	3717	Lime and shale	
3717	TD		Dry and abandoned.

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the SE NW SW Section 36-11S-17W, Ellis County, Kansas, to the best of my knowledge and belief.

E. E. Hall

E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 10 day of February, 1970, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires Feb. 1, 1972

Barbara J. Layton
 Barbara J. Layton, Notary Public

