

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Ellis County, Sec. 36 Twp. 11 Rge. (E) 17 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SE NE/4

Lease Owner Brunson Drilling Co., Inc. et al

Lease Name Planters State Well No. 1

Office Address 333 1st National Bank Bldg. Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 5/8 19 51

Application for plugging filed 5/9 19 "

Application for plugging approved 5/9 19 "

Plugging commenced 5/9 19 "

Plugging completed 5/9 19 "

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	107'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged back with crushed rock from 3351' to 3341'. Dumped 5 sax cement at 3341' with dump bailer, top of cement 3306'. Filled hole with mud to 107', set rock bridge, dumped 10 sax cement for cap.

5-22-51

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Brunson Drilling Company, Inc.
Address Above

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Ralph B. McLaughlin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. Brunson Drilling Company, Inc.

(Signature) *Ralph B. McLaughlin*
333 1st National Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 21st day of May, 19 51

Plugging
Notary Public.

My commission expires September 23, 1953

PLUGGING
FILE SEC 36T 11R 17W
BOOK PAGE 12 LINE 14

BRUNSON DRILLING COMPANY, INC. et al

Well: Planters State #1

SE SE NE/4 Section 36-11-17
Ellis County, Kansas

Commenced RD: 4/27/51
Completed RD: 5/8/51
Total Depth: 3551'

Elevation: 1978' D.F.
Initial Prod.
Contractor: Brunson Drlg. Co., Inc.

Casing: 107' 8 5/8" OD 3rd thd. 24#

STRATA	DEPTH
Shale	400
Redbed & Shale	500
Sand	600
Pyrite & Shale	695
Sand	720
Redbed, Shale & Pyrite	810
Shale & Sand	1025
Sand	1080
Shale & Sand	1158
Anhydrite	1195
Shale & Shells	1525
Sand	1735
Shale & Lime	1795
Broken Lime	1910
Lime	2065
Lime & Shale	2215
Lime	2300
Lime & Shale	2385
Broken Lime	2480
Lime & Shale	2595
Shale & Lime	2950
Lime & Shale	3155
Lime	3287
Lime & Shale	3335
Lime	3478
Conglomerate	3488
Chart, Shale & Lime	3510
Arbuckle	3551
Total Depth	3551

TOPS

Heebner	3150 (-1176)
Lansing	3198 (-1284)
Conglomerate	3487 (-1495)
Arbuckle	3514 (-1540)

RECEIVED
STATE CORPORATION COMMISSION
MAY 22 1951
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

BRUNSON DRILLING COMPANY, INC.
By

R. B. McLaughlin
R. B. McLaughlin, Asst. Sec.

Signed and sworn to in my presence this 21st day of May, 1951, by R. B. McLaughlin, Asst. Secretary of the Brunson Drilling Company, Inc., a corporation in the State of Kansas.

PLUGGING
FILE SEC 36 T 11 R 7th
BOOK PAGE 87 LINE 14

Edmund C. Combs
Notary Public

My commission expires September 23, 1953.