


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Ellis County, Sec. 3 Twp. 11 Rge. 18 (E) W (W)

Give Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Blitting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Flat

Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines \_\_\_\_\_  
Lease Owner National Cooperative Refinery Association  
Lease Name Warner Well No. 1  
Office Address 820 Union National Bank Building  
Character of Well (completed as Oil, Gas or Dry Hole) Abandoned.  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed 6-25- 1952  
Application for plugging approved 6-25 1952  
Plugging commenced 6-25 1952  
Plugging completed 6-30 1952  
Reason for abandonment of well or producing formation Low Production and casing broke in at 860'.  
If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well Eldon Pettie, Hays, Kansas  
Producing formation Kansas City Lime Depth to top 3450 Bottom 3464 Total Depth of Well 3683 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				10 3/4"	214'	Cemented 125 Sx.
				5 1/2"	3628'	861'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Lane Well Bridge plug set at 3482'. Filled hole w/chat from 3482 to 3440; Dumped 4 sacks of mixed cement at 3440'. Filled w/mud from top of cement to 214'. Set plug at 214'. Filled w/rock to 200 ft. dumped 20 sacks of cement. Mud to 25'. Rock Bridge and 10 sacks of cement to top of hole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor National Cooperative Refinery Association  
Address 820 Union National Bank Building  
Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
James C. Hogwood (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) James C. Hogwood  
820 Union National Bank Building  
(Address)

SUBSCRIBED AND SWORN to before me this 7th day of July, 1952.  
J. A. Lange Notary Public.

My commission expires February 20, 1953.

23-8390-s 6-51-20M  
**PLUGGING**  
FILE SEC 3 Twp 11 R 18  
BOOK PAGE 19 LINE 23

April 15, 1948

DRILLING LOG

*to NCLB*

National Cooperative  
Refinery Assn. et al.,  
Union Natl. Bank Bldg.  
Wichita, Kansas

Lease: Warner #1

County: Ellis, Kansas  
Sec. 3-11-18  
Location: 330' S of NL  
330' W of EL  
(NE NW)

Total Depth: 3630'  
Comm: 3-23-48 Comp: 4-14-48  
Shot or Treated  
Casing: 10 3/4" at 214', 5" @ 3628'

Contractor: Gabbert & Lindas Drilling Co., Inc.  
1316 Union National Bank Bldg,  
Wichita 2, Kansas

Figures Indicate Bottom of Formations:

0	to	75	Lime	2165	to	2465	Lime
75		214	Shale	2465		2605	Lime & Shale
214		520	Shale & Lime Streaks	2605		2690	Lime
520		900	Shale & Sand	2690		2910	Lime & Shale
900		1050	Sand	2910		3015	Shale
1050		1110	Shale & Shells	3015		3237	Shale & Lime
1110		1145	Lime	3237		3285	Lime
1145		1265	Red Bed	3285		3385	Lime & Shale
1265		1381	Shale & Sand	3385		3441	Lime
1381		1436	Lime	3441		3482	Lime & Shale
1436		1555	Shale & Lime	3482		3606	Lime
1555		1755	Shale & Shells	3606		3613	Cherty Lime
1755		1920	Shale	3613		3627	Lime & Green Shale
1920		1990	Lime				
1990		2165	Lime & Shale	3627		3630	T.D. Lime

STATE OF KANSAS )  
 ) SS  
COUNTY OF SEDGWICK )

I, the undersigned, being duly sworn on oath state that the above statement and log is true and correct record of the well drilled at the location above described.

GABBERT & LINDAS Drilling  
Company Inc.

By *Scott Stucky*

Subscribed and sworn to before me this 15 day of April, 1948

My commission expires

*Catherine Darcy*  
Notary Public

My commission expires March 25, 1952

RECEIVED  
STATE CORPORATION COMMISSION

MAY 2 1948

CONSERVATION DIVISION  
Wichita, Kansas

**PLUGGING**  
FILE SEC 3 T 11 R 18  
PAGE 14 LINE 23