

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 1 1965  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Beardmore Drg Co  
Complete Address: 700 One Twenty Bldg Wichita, Kans  
Lease Name Casey Well No. 1  
Location SE SE NW Sec. 36 Twp. 17 Rge. (E) (W) 21  
County Ness Total Depth 4200  
Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A x  
Other well as hereafter indicated:       
Plugging Contractor: Omega Drg Co & Globe Cementing Co  
Address:      License No.       
Operation Completed: Hour 10AM Day 25 Month 8 Year 65

The Above well was plugged as follows:

8 5/8" 415' circulated with cement.  
Circulated hole with heavy mud, set plug at 540', displaced 20 sax  
cement through drill pipe, heavy mud to 240', set plug and displaced  
20 sax cement through drill pipe, heavy mud to 40', set plug, hulls and  
filled to bottom cellar with cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 9/1/65  
INV. NO. 1735-W

Signed: [Signature]  
Well Plugging Supervisor