

15-135-20029-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

MAY 22 1967
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Leben Drilling, Inc., etal

Complete Address: 815 Wichita Plaza Wichita, Kansas

Lease Name Hair Well No. 1

Location App. C NW SE Sec. 9 Twp. 17 Rge. 22 (E) (W) X

County Ness Total Depth 4527

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Co Tools

Address: License No.

Operation Completed: Hour 1:30 PDay 20 Month 5 Year 1967

The Above well was plugged as follows:

RTD 4527 8 5/8 csg set at 249' cwc 175 sc.
Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 25 sc cem.
thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 8 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

DATE 5/22/67
INV. NO. 5258-4

Signed: [Signature]
Well Plugging Supervisor