

15-135-20003-00-00

Form CP-3  
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 21 1972  
CONSERVATION DIVISION  
Wichita, Kansas  
01-21-1972

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Beardmore Oil, Inc.  
Complete Address Suite 700 One-Twenty Bldg., Wichita, Kansas 67202  
Lease Name Horchem Well No. 1  
Location SW SW Sec. 35 Twp. 16 Rge. (E) (W) 24  
County Ness Total Depth 4507'  
Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Pipe Pullers, Inc.  
Address Box 486 Ellinwood, Kansas 67526 License No. 462  
Operation Completed: Hour XX 2:30P Day 19 Month 1 Year 1972

The above well was plugged as follows:

Total Depth 4507' 8 5/8 csg set at 202' cwc 175 sk.  
5 1/2 csg set at 4424' cw 100 sk cmt.  
5 1/2 csg perf. (4488)  
Filled 5 1/2 csg W/sd (4450-4507) Dumped 5 sk cmt W/dump bailer. (4415-4450)  
Cutoff and recovered 2717' of 5 1/2 csg.  
Pumped down 8 5/8 csg with 15 sk gel & water W/300 lbs hulls, -70 sk 50-50 poz cmt  
W/6% gel, -10 sk gel & water, -released plug and pumped 50 sk 50-50 poz cmt  
6% gel.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey  
Well Plugging Supervisor

DATE 1-21-72  
INV. NO. 5048-W