

15-135-20759-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 15 1974
07-15-1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Publishers Petroleum

Complete Address Box 25125 Oklahoma City, Oklahoma 73125

Lease Name Horchem Well No. 1

Location SW NE SW Sec. 35 Twp. 16 Rge. (E) (W) 24

County Ness Total Depth 4501'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pumping

Address Box 364 Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 2:30 P: Day 12 Month 7 Year 1974

The above well was plugged as follows:

Total Depth 4501' 8 5/8 csg set at 455' cwc 300 sk.

5 1/2 csg set at 4500' cw 150 sk. & perf. (4488)'

Filled 5 1/2 csg with sand (4501-4475) dumped 4 sk cmt W/dump bailer. (4445-4475)

Cutoff and recovered 2993' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls -released 8 5/8 plug

& pumped 80 sk cmt -displaced with 8 sk gel & water & capped with 20 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Z. Masouf
Well Plugging Supervisor

INVOICED

DATE 7/16/74
J. NO. 9526-W