

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 21 1978
02-21-1978
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 135-21407-00-00 (of this well)

Operator's Full Name Pickrell Drilling Company

Complete Address 205 Litwin Bldg., Wichita, Kansas 67202

Lease Name Sidebottom "B" Well No. 1

Location SW SW Sec. 33 Twp. 16 Rge. (E) (W) 24

County Ness Total Depth 4509'

Abandoned Oil Well Gas Well Input Well SWD Well D & A Y

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 1 P Day 17 Month 2 Year 1978

The above well was plugged as follows:

Total Depth 4509' 8 5/8 csg set 215' cwc 150 sk.

4 1/2 csg set 4488' cw 200 sk cmt.

Filled 4 1/2 csg W/sd (4509'-4470') dumped 3 sk cmt W/dump bailer. (4470'-4440')

Cutoff & recovered 3025' of 4 1/2 csg.

Allied Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water -followed with 70 sk 50-50 poz 6% -displaced with 10 sk gel & water & capped with cementing plug & 70 sk 50-50 poz 6% & shutin. FPP 300 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

Date 2-21-78
INV. NO. 6796-W