

15-135-20046-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

AUG 2 1967

07-31-1967
STATE CORPORATION COMMISSION
WICHITA, KANSAS

Operator's Full Name Mull Drilling Co. Inc.

Complete Address: 1625 Wichita Plaza Wichita, Kansas

Lease Name Miller Well No. 1

Location C NE NE Sec. 33 Twp. 16 Rge. 24 (E) (W) X

County Ness Total Depth 4532

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Donelson Drilling Co.

Address: Wichita, Kansas License No.

Operation Completed: Hour 7 A Day 28 Month 7 Year 1967

The Above well was plugged as follows:

RTD 4532 8 5/8 csg set at 289' cwc 190 sc.
Gunned pits, circulated heavy mud, set cementing plug at 870' and displaced 90 sc cem.
thru drill pipe. Heavy mud to 280' set cementing plug and displaced 25 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 8 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 7/31/67
INV. NO. 6039-W

Signed: [Signature]
Well Plugging Supervisor