

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
APR 2 1965
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Fred J. Haynes Oil Co 1505102530.0000
Complete Address: Bldg & Loan Bldg Russell, Kans
Lease Name Froelich Well No. B-1
Location SW SE SW Sec. 3 Twp. 13 Rge. (E) (W) 16
County Ellis Total Depth 3489
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Barnes & Sons & United Cementing Co
Address: Russell, Kans License No.
Operation Completed: Hour 3:30PM Day 30 Month 3 Year 65

The Above well was plugged as follows:

8 5/8" 190' circulated with cement - 4 1/2" 3489' PB to 3190' Perf 31 1/8'
Filled with sand to 3160', set 4 sax cement with dump bailer pulled
2777' 4 1/2" to 550', circulated hole with heavy gel mud through 4 1/2" at
550' (25 sax Gel), displaced 20 sax cement through 4 1/2" at 480', heavy
mud to 180', displaced 20 sax cement through 4 1/2" at 180', heavy mud to
35', cement 35' to 0'

Mudding and cementing by United Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edwin Peery
Well Plugging Supervisor

DATE 4/2/65

INV. NO. 916-W