

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 15:051:060040000

LOCATION CN $\frac{1}{2}$  NW NE

SEC. 32 TWP. 11 RGE. 17 W

Dry Hole \_\_\_\_\_ Abandoned Oil Well x Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease \_\_\_\_\_ Shutts \_\_\_\_\_

Operator Barnett Oil Co Address Wichita, Kans *417 1st Natl. Bank Bldg.*

Field Bemis County Ellis

Total Depth 3631 Feet.

(Describe briefly the manner in which the well was plugged)

10 3/4" at 1208' circulated with 450 sax cement - 5 1/2" at 3597'  
with 100 sax cement behind - Lane Wells plugs at 3436', 3403 & 3397'  
Top perforations at 3377' - Filled with chat to 3370', set 4 sax  
cement with dump bailer - pulled approx 3200' 5 1/2", filled hole with  
mud to 300', set rock bridge and 20 sax cement, mud to 40', set rock  
and 10 sax cement to bottom cellar.

4-10-52

**PLUGGING**  
FILE SEC 32 TWP 11 R 17 W  
BOOK PAGE 8 LINE 10

*[Signature]*  
District Conservation Agent

Date 4-3-52