

15-051-04791-0000
DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 19-55
LOCATION NW NE NW
SEC. 02 TWP. 11 RGE. 17

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Hadley
Operator Great Lakes Carbon Address Wichita, Kans
Field Bemis County Ellis
Total Depth 3547 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 937' circulated with cement - 5 1/2" at 3531 with
90 sax cement behind. 4" liner to 3479' cemented in, top
perforation at 3341'.

Filled with mud and chat to 3320', set ^{5"}4" sax cement with
dump bailer, pulled 2700' 5 1/2", filled with mud to 250',
set rock bridge and 15 sax cement, filled with heavy mud
to 40', set rock bridge and 10 sax cement to bottom cellar.

ANG 28 1950

PLUGGING
FILE SEC 32 T. 11 R. 17
BOOK PAGE 19 LINE 35

John S. Strach
District Conservation Agent

Date 8-23-50