

15-05103616-0000
DISTRICT CONSERVATION AGENT'S REPORT

BR

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 24-45

LOCATION NW SE SE

SEC. 32 TWP. 11 RGE. 17

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 4 Lease _____ Kessler _____

Operator Phillips Pet Co. Address Great Bend, Kans

Field Bemis County Ellis

Total Depth 3524 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 958' circulated with 50 sax cement - 5 1/2" at
3524' with 150 sax cement behind - Baker plugs at 3340' with
4 sax calseal - top perf 3224'.

Set Halliburton plug at 3200', rock and 5 sax cement run with
dump bailer, pulled 1550' 5 1/2", filled hole with mud to 500',
set rock and 15 sax cement, mud to 35', rock and 10 sax
cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION

JUL - 2 1952

J. Gordon Peeler
District Conservation Agent

Date 7-1-52

PLUGGING
FILE SEC 37 11 17
BOOK PAGE 29 LINE 45
CONSERVATION DIVISION
Wichita, Kansas