

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 24 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Rocket-Schusterman Oil Acct.
Complete Address 1209 Mid Continent Bldg., Tulsa, Okla.
Lease Name Samuelson Well No. 7
Location SW NW NW Sec. 36 Twp. 11 Rge. (E) (W) 17
County Ellis Total Depth 3683
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Gabbert-Jones
Address Wichita, Ks. License No.
Operation Completed: Hour 2:30A Day 21 Month 2 Year 1970

The above well was plugged as follows:

RTD 3683' 8 5/8 csg set at 251' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo. F. Mansour
Well Plugging Supervisor

INDEXED
DATE 2/25/70
INV. NO. 1488-W