


KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
NOV 6 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name High Plains Production Co.

Complete Address: 304 Insurance Bldg., Wichita, Kansas

Lease Name Planters Bank Well No. 1

Location NE NW NE Sec. 36 Twp. 11 Rge. 17 (E) (W) X

County Ellis Total Depth 3700' 3639'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated: _____

Plugging Contractor: Sage Drlg.

Address: Wichita, Kansas License No. _____

Operation Completed: Hour 8:30A Day 3 Month 11 Year 1968

The Above well was plugged as follows:

RTD 3700' 8 5/8 csg set at 290' cwc. Cmt. Mat. 50-50 poz cmt. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sc cmt.

thru drill pipe. Heavy mud to 270' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cmt. to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. A. Mearns
Well Plugging Supervisor

DATE: 11/6/68
INV. NO. 8774-4