

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 9 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Rocket - Schusterman Oil Account

Complete Address 1209 Mid Continent Bldg., Tulsa, Okla.

Lease Name Hall "C" Well No. 3

Location SE NW SW Sec. 36 Twp. 11 Rge. (E) (W)17

County Ellis Total Depth 3716'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Gabbert - Jones

Address Wichita, Kansas License No.

Operation Completed: Hour 8:45A Day 7 Month 2 Year 1970

The above well was plugged as follows:

RTD 3716' 8 5/8 csg set at 252' cwc Cmt. Mat. 50-50 poz cmt W/6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk cmt

thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base

of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Paul F. Mearns
Well Plugging Supervisor

DATE 2/9/70
INV. NO. 1387-W