

State of Kansas



15-135-20804-00-00

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)RECEIVED  
STATE CORPORATION COMMISSION

SEP 27 1974

CONSERVATION DIVISION  
Wichita, Kansas

09-27-1974

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Darrell Kelso of Kelso Casing Pulling has this  
date requested permission to plug the following described well:Mr. Kelso guarantees payment of the plugging fee.Operator's full Name: Chief Drilling Company, Incorporated,Complete Address: 905 Century Plaza, Wichita, Kansas.Lease Name: R.B.B. Well No. 1Location: SE-NW-NW Sec. 23 Twp. 17 Rge. (E)(W) 21County: Ness Total Depth 4102 Oil Well XGas Well      Input Well      SWD Well      D & A      Lost Hole     Mr. Kelso was instructed to plug the well as follows:290'--8 5/8" Surface casing, cement circulated with 185 Sx.  
4099'--5 1/2" Production casing cemented on bottom with 125 Sx. Top of  
perforations @ 4083'.Sand well back to 4050' and set 4 Sx. cement with dump bailer. Pull 5 3/4"  
casing and squeeze well with 5 sacks hulls, 20 sacks gel and 150 Cu. Ft.  
cement, staged.

Very truly yours,

Conservation Division Agent