

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS, 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION

MAR 20 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Burris of Warrior Drlg. has this

date requested permission to plug the following described well:

Mr. Burris guarantees payment of the plugging fee.Operator's full Name: Chief Drlg. Co., Inc.Complete Address: 905 Century Plaza, Wichita, Ks.Lease Name: Elmore Well No. 1Location: C SE SW Sec. 17 Twp. 17 Rge. (E)(W) 25County: Ness Total Depth 4510' Oil Well Gas Well Input Well SWD Well D & A XX Lost Hole Mr. Burris was instructed to plug the well as follows:RTD 4510' 8 5/8 csg set 268' cwc 225 sk. Flg. Mat. 50-50 poz 6 1/2 total gel.Gun pits, circulate heavy mud, set 70 sk cmt plug at 720' thru drill pipe.Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Red Messer
Conservation Division Agent