

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 11 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Cain of Strata Drlg. has this

date requested permission to plug the following described well:

Mr. Cain guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drlg., Inc.

Complete Address: Box 18407 Wichita, Kas.

Lease Name: Stutz "I" Well No. 1

Location: C NE SW Sec. 7 Twp. 17 Rge. (E)(W) 25

County: Ness Total Depth 4534' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Cain was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 750' and displace

70 sk cmt thru drill pipe. Heavy mud to 270' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo R. Massey
Conservation Division Agent