

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

APR 8 - 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Swope of Phillips Petro. has this

date requested permission to plug the following described well:

Mr. Swope guarantees payment of the plugging fee.

Operator's full Name: Phillips Petroleum Co.

Complete Address: Box 287 Great Bend, Kansas

Lease Name: Mollenkamp Well No. 1 -AB

Location: 1980' FWL & 660' FSL SW/4 Sec. 4 Twp. 17 Rge. (E)(W) 25

County: Ness Total Depth 4510' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Swope was instructed to plug the well as follows:

Gun pits, circulate heavy mud, displace 75 sk cement plug (4502-4302)

Displace 50 sk cement plug (1180'-1030')

Displace 50 sk cement plug (357'-257')

Set cementing plug & 1/4 sk hulls at 40' -fill to surface with 10 sk cem.

Very truly yours,

Leo J. Manning
Conservation Division Agent