

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-135-19077-00-00 (of this well) 6/87
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Phillips Petroleum Company OPERATORS LICENSE NO. 5229

ADDRESS Route #3, Box 20-A Great Bend, Kansas 67530 PHONE # (316) 793-8421

LEASE (FARM) Ummel "AB" WELL NO. 2 WELL LOCATION NE/4 NW/4 COUNTY Ness

SEC. 11 TWP. 17N RGE. 22 or (W) TOTAL DEPTH 4485' PLUG BACK TD 4485'

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 228' CEMENTED WITH 150 SACKS

CASING SIZE 5 1/2" SET AT 4474' CEMENTED WITH 75 SACKS

PERFORATED AT Open hole 4475'-85'

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Sand back to 4420, w/ 5 SX CMT on top,
pull 5 1/2" csg, pump 2 sx Hulls, 15 sx Gel, 50 sx cmt, 10 sx Gel, 1 sx Hull, rubber
wiper plug, and 150 sx cmt. Fill backside to surface if necessary.
(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? IS ACO-1 FILED?
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:
G. L. Kelso PHONE # (316) 793-8424

ADDRESS Route #3, Box 20A Great Bend, Kansas 67530

PLUGGING CONTRACTOR None LICENSE NO. _____

ADDRESS _____ PHONE # () _____

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: [Signature]
(Operator or Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 11 1987
5-11-87
CONSERVATION DIVISION
Wichita, Kansas
DATE: _____

5-8-87

①