

15-101-30000-00-00


WELL PLUGGING RECORD

Give All Information Completely
Make Correct Affidavit
Mail Deliver Report to:
Conservation Division
State Corporation Commission
1000 Broadway
Topeka, Kansas

Lane County, Sec. 12 Twp. 16 Rge. 27 (E) W (W)

Location as "NE/CNW/SW" or footage from lines C SE SE
Lease Owner Morrison Producing Company
Lease Name Evel Well No. 1
Office Address El Dorado, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 6-1-65 _____ 19____
Plugging completed 6-3-65 _____ 19____
Reason for abandonment of well or producing formation Depleted.
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4535 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	110'	None
				5-1/2"	4534'	2754'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to plug back @ 3935' and dumped 5 sacks of cement @ 3935' with dump bailer. Pulled 5 1/2" casing to 560' and dumped 25 sacks of gel mud @ 560'. Pulled 5 1/2" casing to 475' and pumped in 20 sacks of cement. Pulled 5 1/2" casing to 200' and pumped in 20 sacks of cement. Pulled balance of 5 1/2" casing, mudded hole to 35', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

STATE CORPORATION COMMISSION

JUL 12 1965

PLUGGING COMPLETE.

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas

SUBSCRIBED AND SWORN TO before me this 11th day of June 1965

Milton J. Volin

My commission expires May 20, 1968

Notary Public

15-101-30000-00-00

DRILLER'S LOG

COMPANY: Funk & Morrison
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: EVEL #1
 LOCATION: C SE SE Sec. 12-16S-27W
 LANE COUNTY, KANSAS
 COMMENCED: 4-22-65
 COMPLETED: 5-4-65

0	20	Sand
20	102	Post Rock & Shale
102	1865	Shale
1865	1990	Shale & Redbed
1990	2030	Anhydrite
2030	2755	Shale
2755	3040	Shale & Lime
3040	3200	Lime & Shale
3200	3472	Shale & Lime
3472	3912	Lime & Shale
3912	4535	Lime
	<u>4535</u>	<u>RTD - Set 5 1/2" Casing</u>

MAILED
 MAY 10 1965
 COUNTY OF BARTON

Set 8 5/8" used surface casing @ 102' cemented with 125 sacks 60-40 Posmix Sunset

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Evel #1 well, located C SE SE of Section 12, Township 16 South, Range 27 West, Lane County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 7th day of May, 1965.

Ulanda Nichols

Ulanda Nichols

My Commission Expires:
 April 1, 1967