

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-101-20897-00-00

LEASE NAME Evel

WELL NUMBER #2

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 12 TWP. 16S RGE. 27W (E) or (W)

COUNTY Lane

Date Well Completed

Plugging Commenced 10-12-99

Plugging Completed 10-14-99

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Joe Gerstner Oil Company

ADDRESS 302 E. Sycamore Ness City, Kansas 67560

PHONE#(785) 798-5466 OPERATORS LICENSE NO. 9615

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Mike Maier (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.O. 4531'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	300'	None
				5-12/2"	4530'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s Plugged off bottom with sand to 4080' and 5 sks. cement. Shot pipe @1250', ran tubing to 2000' and pumped 60 sks. cement and 300# hulls, pulled up to 1250', pumped 100 sks. cement, and 200# hulls, pulled tubing out, tied onto 8-5/8" surface and pumped 100 sks cement, Tied onto 5-1/2" casing, pumped 100 sks. cement, 60/40pos. 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Joe Gerstner Oil Company

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

RECEIVED
 STATE CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 20th day of October, 1999

Oct 9, 1999

[Signature]
 Notary Public

CONSERVATION DIVISION
 Wichita, Kansas My Commission Expires:

IRENE HERZBERG
 State of Kansas
 My Appt. Exp. Aug. 24, 2001

Form CP
 Revised 05-