

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-009-04899-0000

LEASE NAME Hulme

WELL NUMBER "G" #1

990 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 16 TWP. 20 RGE 12 (E) or (W)

COUNTY Barton

Date Well Completed 1-18-57

Plugging Commenced 11-15-90

Plugging Completed 11-26-90

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Rockhold Engineering, Inc.

ADDRESS Box 698, Great Bend, Ks. 67530

PHONE # (316) 792-2506 OPERATORS LICENSE NO. 5111

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on November 26, 1990 (date)

by Gilbert Scheck (KCC District Agent's Name).

Is ACO-1 filled?                      If not, Is well log attached? With application

Producing Formation                      Depth to Top                      Bottom                      T.D. 3456'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	240'	None
				5-1/2"	3423'	2,557.68'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from        feet to        feet each set. Dump 5 sacks cement on bottom, sand to 3100' and 5 sacks cement. Shot casing 2915', 2724', 2631' and 2535'. Pulled 86 joints of 5-1/2" casing. B.J. Services plugged well with 500# hulls and 200 sacks 60/40 pozmix with 8% gel, Maximum pressure 600 psi and shutin 400 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Ks. 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Rockhold Engineering, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

NOV 27 1990

(Signature) James W. Rockhold

James W. Rockhold

(Address) Box 698, Gt. Bend, Ks. 67530

CONS. DIVISION  
WICHITA, KANSAS

SUBSCRIBED AND SWORN TO before me this 26th day of November, 1990

Jona M. Leatherman

Notary Public

My Commission Expires:



